BRUHATH BANGALORE MAHANAGARA PALIKE
Yelahanka Zone, Yelahanka Division

Executive Engineer
Yelahanka Division
BBMP, Bangalore-64

Approved Tender Schedule - B

Name of Work:-Construction of concrete drains and concrete roads at Rajiv Gandhinagar in Attur ward no-03.

Sl. No	Description	Unit	Approved qty	Approved Rate	
				Rate	Rate in words
1	Removing B.S slab of drain and stacking	sqm	399.30	63.72	Rupees sixty three and paise seventy two
2	Refixing stone slabs of drains and pointing in CM(1:3)	Sqm	399.30	78.84	Rupees seventy eight and paise eighty four only
3	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick	Sqm	326.70	663.12	Rupees six thousand sixty three and paise twelve only
4	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3.	Cum	341.40	83.16	Rupees eighty three and paise sixteen only

Please write or type below this line

5	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification.	Cum	34.56	288.36	Rupees two hundred eighty eight and paise thirty six only
6	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no	Cum	43.26	5070.60	Rupees five thousand seventy and paise xity only
7	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification	Cum	7.68	4135.32	Rupees four thousand one hundred thorty five and paise thirty two only
8	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (P.23/5.9)	Cum	7.20	4905.36	Rupees four thousand nine hundred five and paise thirty six only

Please write or type below this line

9	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	19.20	99.36	Rupees ninety nine and paise thirty six only
10	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge o	Cum	4.95	6198.12	Rupees six thousand one hundred ninety eight and paise twelve only
11	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3	Tonne ,s	0.50	70509.96	Rupees seven thousand five hundred nine and paise ninety six only
12	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecification S.Specification no.KBS 4.6.2	Sqm	7.50	306.72	Rupees three hundred six and paise seventy two only
13	KSRB M2200-5.11.Design mix M20 with OPC cement @320 kgs,with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999 Reaffirmed-2008.etc as per specification&direction of the engineer incharge of work	Cum	36.45	6732.72	Rupees six thousand seven hundred thorty two and paise seventy two only

Please write or type below this line

14	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator,HOM of machinery screed vibratory,power floater,blade and disk etc,,with all lead and lift etc as per specifications	Sqm	250.00	97.20	Rupees ninety seven and paise twenty only
15	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine,generator&HOM of machinery,including cost of blade,coolant etc as per specifications as per	Rmtr	25.00	124.20	Rupees one hundred twenty four and paise twenty only
16	KSRRB M100-1 Loading and un loading of stone boulder/Stoneaggregates/sand/kanker/ Moorum. KSRRB M100-1:Placing tipper at loading point,loading with front end loader, dumping, turning for return trip,excluding time for haulage and return trip complete as per specifications	Cum	375.96	68.04	Rupees sixty eight and paise four only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the contractor

Executive Engineer
Yelahanka Division
BBMP, Bangalore-64

Please write or type below this line